

**PROFORMA REGARDING SAFE DRINKING WATER AND SANITARY
CONDITION CERTIFICATE**

No. 3929

Date: 13/08/26

It is certified that an inspection team headed by Deputy Cmo G.B. Nagar. **ASPAM Scottish School, A-43, Sector-62, Noida, G.B Nagar.** on dated 13-08-2026 and found that the **ASPAM Scottish School** has safe drinking water facilities for the students and members of staff of the institution and is maintaining the hygienic sanitation condition in the school building & the campus as per the norms prescribed by the Central/State/U.T. Govt.

The above valid for a period of 1 Year.

Signature with Seal:-

Name:-

Dr. Madan Mohan Mani Tripathi

Designation:-

Chief Medical Officer

To

The Principal,
ASPAM Scottish School,
A-43, Sector-62, Noida,
Gautam Budh Nagar.


TEST REPORT

Issued To : Aspam Scottish School
 A-43, Sector 62
 Noida,, Uttar Pradesh - 201301

Report No: 11-130826-01
Report Date: 19/08/2026
Sample Received On : 13/08/2026
Sampled By: AES Labs (SM 1.4)

Description : Drinking Water, Sample Quantity: 3Ltr in Plastic Can & 200ml in sterilized Bottle

Analysis Start Date : 13/08/2026
Analysis End Date : 19/08/2026

Page 1 of 2

Analysis of Drinking Water as per IS 10500:2012
RESULTS

S.No.	Parameter	Test Method	Results	Units	Limits	Extended Limits
Chemical						
Residues in Water						
General Parameters Concerning Substances Undesirable in Excessive Amounts						
1	Iron (as Fe)	IS 3025: (Pt-65):2025	BLQ (<0.002)	mg/l	Max 1.0	No Relaxation
Water						
Organoleptic and Physical Parameters						
2	pH Value	IS 3025: (Pt-11):2022	7.46	-	6.5-8.5	No relaxation
3	Turbidity	IS 3025: (Pt-10):2023	<1.0	NTU	Max 1	Max 5
4	Total Dissolved Solid	IS 3025: (Pt-16):2023	143.0	mg/l	Max 500	Max 2000
General Parameters Concerning Substances Undesirable in Excessive Amounts						
5	Chloride	IS 3025: (Pt-32):1988	63.98	mg/l	Max 250	Max 1000
6	Sulphate (as SO ₄ /SO ₃)	IS 3025: (Pt-24):2022	2.4	mg/l	Max 200	Max 400
7	Alkalinity (as CaCO ₃ / HCO ₃)	IS 3025: (Pt-23):2023	8.08	mg/l	Max 200	Max 600
8	Total Hardness (as CaCO ₃)	IS 3025: (Pt-21):2009	9.09	mg/l	Max 200	Max 600
9	Permanent Hardness (as CaCO ₃)	IS 3025: (Pt-21):2009	8.08	mg/l		
10	Calcium Hardness (as CaCO ₃)	APHA 3500 Ca (B):24thED	6.06	mg/l		
11	Magnesium Hardness (as CaCO ₃)	APHA 3500-Mg (B):24thED	3.03	mg/l		
12	Phenolphthalein Alkalinity	IS 3025: (Pt-23):2023	BLQ (<1)	mg/l		


AUTHORISED SIGNATORY

NOTE: The results indicated only refer to the tested samples and listed parameters and do not endorse any product | Total liability of the laboratory is limited to the invoiced amount | This certificate shall not be reproduced wholly or in part without prior written consent of the laboratory | Samples received shall be destroyed after four weeks from the date of issue of the certificate unless specified otherwise | This certificate shall not be used in any advertising media or as evidence in the court of law without prior written consent of the laboratory.

AES/QCD/F-7.8-I

**TEST REPORT**

Issued To : Aspam Scottish School
A-43, Sector 62
Noida,, Uttar Pradesh - 201301

Report No: 11-130826-01
Report Date: 19/08/2026
Sample Received On : 13/08/2026
Sampled By: AES Labs (SM 1.4)

Description : Drinking Water, Sample Quantity: 3Ltr in Plastic Can & 200ml
in sterilized Bottle

Analysis Start Date : 13/08/2026
Analysis End Date : 19/08/2026

Page 2 of 2

Analysis of Drinking Water as per IS 10500:2012**RESULTS**

S.No.	Parameter	Test Method	Results	Units	Limits	Extended Limits
13	Silica (as Si)	IS 3025: (Pt-35):2024	BLQ (<0.2)	mg/l		
14	Temporary Hardness (as CaCO3)	APHA 2340 (C):24thED	1.01	mg/l		

Remarks: The tested sample conforms to the specifications of drinking water as per IS 10500:2012 with respect to the above parameters. The conformity decisions are based on guard banded acceptance limits calculated based on the expanded uncertainty of the result (Decision Rule LM 7.8.6). The decision has a confidence level of approximately 95 %, with an error probability of approximately 5%.

Note(s): BLQ means Below Limit of Quantification. The values enclosed in brackets are the limit of Quantification of the mentioned test method.
The above remarks are computer generated.

**** End of Report****

**AUTHORISED SIGNATORY**